



RHODE ISLAND
DEPARTMENT OF ENVIRONMENTAL MANAGEMENT

235 Promenade Street, Providence, RI 02908-5767

TDD 401-222-4462

May 14, 2008

Town of Middletown
Gerald S. Kempen, Town Administrator
350 East Main Road
Middletown, RI 02842

Insignificant Alteration – Permit

RE: Application No. 08-0038 in reference to the property and proposed project located:

Approximately 200 feet west of Valley Street, approximately 300 feet south of the intersection of Valley Street and Connecticut Avenue, Assessor's Plat 108, Lot 554, Middletown, RI.

Dear Mr. Kempen:

Kindly be advised that the Department of Environmental Management's ("DEM") Freshwater Wetlands Program ("Program") has completed its review of your **Request for Preliminary Determination** application. This review included a site inspection of the above referenced property ("subject property") and an evaluation of the proposed police station with associated parking areas, sidewalks, utilities and stormwater control system as illustrated and detailed on site plans submitted with your application. These site plans were received on May 1, 2008.

Our observations of the subject property, review of the site plans and evaluation of the proposed project reveals that alterations of freshwater wetlands are proposed. However, pursuant to Rule 9.00 of the Rules and Regulations Governing the Administration and Enforcement of the Fresh Water Wetlands Act (Rules), this project may be permitted as an **insignificant alteration** to freshwater wetlands under the following terms and conditions:

Terms and Conditions for Application No. 08-0038:

1. This letter is the DEM's permit for this project under the R.I. Fresh Water Wetlands Act, Rhode Island General Laws (RIGL) Section 2-1-18 et seq.
2. This permit is specifically limited to the project, site alterations and limits of disturbance as detailed on the site plans submitted with your application and received by the on May 1, 2008. A copy of the site plans stamped approved by the DEM is enclosed. Changes or revisions to the project which would alter freshwater wetlands are not authorized without a permit from the DEM.
3. Where the terms and conditions of the permit conflict with the approved site plans, these terms and conditions shall be deemed to supersede the site plans.
4. You must notify this Program in writing immediately prior to the commencement of site alterations and upon completion of the project.

5. A copy of the stamped approved site plans and a copy of this permit must be kept at the site at all times during site preparation, construction, and final stabilization. Copies of this permit and the stamped approved plans must be made available for review by any DEM or City/Town representative upon request.
6. The effective date of this permit is the date this letter was issued. This permit expires four (4) years from the date of issue unless renewed pursuant to the Rules.
7. Any material utilized in this project must be clean and free of matter that could pollute any freshwater wetland.
8. Prior to commencement of site alterations, you shall erect or post a sign resistant to the weather and at least twelve (12) inches wide and eighteen (18) inches long, which boldly identifies the initials "DEM" and the application number of this permit. This sign must be maintained at the site in a conspicuous location until such time that the project is complete.
9. Temporary erosion and sediment controls detailed or described on the approved site plans shall be properly installed at the site prior to or commensurate with site alterations. Such controls shall be properly maintained, replaced, supplemented, or modified as necessary throughout the life of this project to minimize soil erosion and to prevent sediment from being deposited in any wetlands not subject to disturbance under this permit.
10. Also prior to commencement of any site alterations, permanent buffer zone markers must be installed along the limit of disturbance at the locations indicated in red ink on the approved site plans, in order to provide permanent reference points on site that are clear to present and future property owners. Acceptable permanent type markers include 4" x 4" pressure treated timber posts, galvanized fence posts with cap, or granite or concrete bounds. Markers must extend a minimum 24" above grade. A permanent-type tag or sign labeled "RIDEM Buffer Zone" must be placed on each marker. A permanent-type fence at least 24" tall placed along the limits of disturbance and similarly labeled may be substituted where desired. **No alterations of any kind are permitted beyond these markers without first obtaining the necessary permit from this Program.**
11. Upon permanent stabilization of all disturbed soils, temporary erosion and/or sediment controls consisting of staked hay bales or silt fencing must be removed.
12. You are responsible for the proper installation, operation, maintenance and stability of any mitigative features, facilities, and systems of treatment and control which are installed or used in compliance with this permit to prevent harm to adjacent wetlands until such time that you document that this responsibility has been assumed by another person or organization.
13. You are obligated to install, utilize and follow all best management practices detailed or described on the approved site plans in the construction of the project to minimize or prevent adverse impacts to any adjacent freshwater wetlands and the functions and values provided by such wetlands.

14. You must provide written certification from a registered land surveyor or registered professional engineer that the stormwater drainage system including any and all basins, piping systems, catch basins, culverts, swales and any other stormwater management control features have been constructed/installed in accordance with the site plans approved by this permit. This written certification must be submitted to this Program within twenty (20) days of its request or upon completion of the project.
15. This Program has made specific revisions to the approved site plans. These revisions are clearly marked in red on the approved plans. Specifically, a) The plan set has been numbered to correspond with the number of plan sheets provided in the set; b) The 0.875-ft diameter dimension provided on the Water Quality Outlet Detail on sheet 10 of 10 shall be drilled into the 6-inch diameter endcap provided for the water quality outlet; c) The area within Perimeter Wetland to be disturbed for installation of the proposed 8-inch sewer line shall have all original grades restored and all disturbed soils shall be seeded with a wildlife conservation seed mix. The Perimeter Wetland shall be allowed to revert to a natural wild state upon completion of the project and these provisions shall be required upon completion of any future sewer line maintenance or repair activities. This project must take place in compliance with these revisions.

Pursuant to the provisions in Rule 7.09 and Rule 11.04, as applicable, any properly recorded and valid permit is automatically transferred to the new owner upon sale of the property.

Kindly be advised that this permit is not equivalent to a determination of the type or extent of freshwater wetlands on the subject property. Should you wish to obtain such verification, you may submit an application in accordance with Rule 8.03.


You are required to comply with the terms and conditions of this permit and to carry out this project in compliance with the Rules at all times. Failure to do so may result in an enforcement action by this Department.

In permitting the proposed alterations, the DEM assumes no responsibility for damages resulting from faulty design or construction.

This permit does not remove your obligation to obtain any local, state, or federal approvals or permits required by ordinance or law and does not relieve you from any duties owed to adjacent landowners with specific reference to any changes in drainage.

Please contact Jane Kelly of this office (telephone: 401-222-6820, ext. 7420) should you have any questions regarding this letter.

Sincerely,



Martin D. Wencek, Permitting Supervisor
Office of Water Resources
Freshwater Wetlands Program
MDW/JEK/jek

Enclosure: Approved site plans