


**LEGEND**

- ⊕ = Water Table Test
- ⊕-1-2 = Percolation Tests
- △ = Proposed Well Location
- = Existing Contours
- = Finish Contours
- BM = Bench Mark - Spike in Tree
- Elevation 105.22
- "Do Not Disturb"
- FW = Proposed Water Line
- = EDGE OF 50' PERIMETER WETLAND



**Installation of Silt Fence**

**EROSION CONTROL NOTES**


1. Prior to any construction or earthwork activity, a line of stacked haybales and/or silt fencing shall be placed as shown and maintained throughout the construction process for each lot.
2. All disturbance is to be limited to the areas shown, and is to be kept to an absolute minimum.
3. All excavated materials (soil) to be used as backfill shall be stockpiled. This stockpiled material shall be surrounded by silt fencing.
4. All excess unwanted excavated materials, construction debris etc., shall be removed from the site and disposed of in a proper manner.
5. No disturbances shall occur below the silt fence/haybale line during construction.
6. All disturbed areas, including backfilled and graded areas shall be loamed and seeded as soon as possible after completion of all construction. All slopes and exposed areas shall be stabilized with straw mulch.
7. All silt fencing/haybales and mulch are to remain in place until after the grass has properly rooted, approximately six to eight weeks.
8. The following seed mix to be used in all disturbed and exposed areas. Before seeding, however, a minimum of four inches of compacted loam is to be placed in the affected areas at a rate of 12.4 cubic yards per 1000 square feet.

**SEED MIXTURE-GENERAL PURPOSE**


SEED MIXTURE	LBS/ACRE	LBS/1000 SF
Red Fescue	75	1.75
Kentucky Bluegrass	15	.35
Colonial Brome	5	.11
Perennial Ryegrass	5	.11

The straw mulch is to be applied at a rate of 90 lbs. per 1000 square feet. The grass seed should be planted between April 1 - June 15 and August 15 - September 30.

**Planting Note:** Evergreen trees will be planted at the limits of disturbance, as indicated on this site plan. Arbor vitae (*Thuja occidentalis*) or white pine (*Pinus strobus*) saplings will be planted 8-10 feet on-center, 5-6 feet in height after plantings. Any plantings not surviving at least one growing season will be replaced.




**PROFILE**  
Scale: None




**TYPICAL TRENCH SECTION**  
NO SCALE


- ELJEN IN-DRAIN NOTES**
1. Bring backfill to elevation 105.71 (see note #1 of the standard notes).
  2. Eljen units to be installed in accordance with the manufacturer's instructions & with the section detail on this plan.
  3. Install 6" of concrete sand directly below the units & 6" around the side wall area to elevation 105.71.
  4. Set Eljen units level per manufacturer's instructions.
  5. Set D-lines (4" perforated pipe, sch. 35.) over center of units & connect at ends. Secure pipes with clamps (1 per unit).
  6. Install filter fabric over the rows of units & hand backfill medium or coarse sand between rows & min. 6" around sides.
  7. Complete backfill & loam per notes. Do not use wheeled equipment over system. Divert surface runoff.





**Location Map**



**D-BOX**  
1000 GALLON TWO COMPARTMENT SEPTIC TANK



**D-BOX**  
1000 GALLON TWO COMPARTMENT SEPTIC TANK



**INVERT SCHEDULE**

1. Sewer line from foundation 106.2
2. Septic tank inlet 106.0
3. Septic tank outlet 105.75
4. D-Box inlet 105.64
5. D-Box outlet 105.48
6. In-Drain Pipe inlet 105.38
7. Bottom of In-Drains 104.8
8. Bottom of trench 104.2

**NOTES**

1. The leaching area extending to 5' on all sides, must be stripped of trees & brush, topsoil, subsoil, and soil containing fines and to at least 4" in depth, and the excavation scarified and backfilled with clean, coarse gravel free of fines dust or debris. Remove all trees and brush to 10' beyond all sides.
2. Gravel backfill shall be brought up to at least TOP OF PIPES (EL. 105.71)
3. All portions of the leaching system shall be a minimum of 100' from any well existing or proposed.
4. There are no existing or proposed wells within 200' of the proposed system. There are no existing or proposed public wells within 500' of the proposed system.
5. There are no existing or proposed sewage systems within 100' of the proposed well.
6. No portion of the ground within 10' of the system shall slope to an elevation lower than the system invert.
7. The surface area over the system shall be grassed.
8. No parking or vehicular traffic on the system surface.
9. Subsurface drains or foundation drains are NOT intended; any drains must be at least 25' from the system. No GARBAGE DISPOSALS ALLOWED.
10. Septic tank to be provided with an inlet or baffle and an outlet tee. A Zobel A-1800 Effluent Filter is required in the outlet tee.
11. Septic tank to have an access manhole to grade with heavy duty cover set to divert surface water away.
12. ALL WORK TO BE DONE DURING THE DRY SEASON.


**ZONING CLASSIFICATION**  
SETBACKS: Front Side Rear

**SOIL TEST DATA - DEH FILE 0811-0954**

Test Hole	Surface Elevation	Depth	Soil Description
1	103.1		
2	103.8		

SEE REPORT

Max. Ground Water Depth	Verified Water Table
2'	2'



Scale: 1" = 20'

**PROPOSED SEWAGE DISPOSAL SYSTEM**

Owner: CHRISTOPHER WHITTAKER

Site: AP 28 Block 7 Lot 7  
ESCOHEAG HILL ROAD

Town: ELLER

DEPARTMENT OF ENVIRONMENTAL MANAGEMENT  
OFFICE OF WATER RESOURCES  
FRESHWATER WETLANDS PROGRAM  
VIEWED SITE PLAN APPLICATION NO. 18-034  
DATED FEB 08 2009  
LETTER OF SAME DATE.

EUGENE F. SPRING  
REGISTERED PROFESSIONAL ENGINEER  
No. 3166

**OWTS AREA**

3 BEDROOM DESIGN  
@ 115 GPD = 345 GPD  
SOIL CATEGORY 6  
MINIMUM AREA  
345 / .61 = 565.57 SF

**PROVIDED AREA**

21 EUBEN 28 SF = 588 SF

**DESIGN OUT - 2**

EL. 102.8 - 2 = 101.8  
+ 3' TO BOTTOM OF ELJEN  
= 104.8