



RHODE ISLAND

DEPARTMENT OF ENVIRONMENTAL MANAGEMENT

235 Promenade Street, Providence, RI 02908-5767

TDD 401-222-4462

January 8, 2016

Middle Creek Farm, LLC
c/o Michael Behan
975 Aquidneck Avenue
Middletown, RI 02842

Insignificant Alteration - Permit

Re: Wetlands Application No. 15-0187; and RIPDES No. RIR101318 in reference to the location below:

Approximately 1000 feet south of Old Mill Lane and approximately 500 west of the terminus of Cornelius Drive, Assessors Plat 128, Lot 73 in Middletown, and Assessors Plat 68, Lot 71 in Portsmouth, RI.

Dear Mr. Behan:

Kindly be advised that the Department of Environmental Management's ("DEM") Freshwater Wetlands Program ("Program") has completed its review of your **Request for Preliminary Determination** application. This review included a site inspection of the above referenced property ("subject property") and an evaluation of the proposed construction of an 11-lot residential subdivision with paved culdesac road, onsite wastewater treatment systems (OWTS), stormwater management systems that includes two detention basins and rain gardens, utility lines, and landscaped yards, as illustrated and detailed on site plans submitted with your application. These site plans were received by the DEM on January 5, 2016.

Our observations of the subject property, review of the site plans and evaluation of the proposed project reveals that alterations of freshwater wetlands are proposed. However, pursuant to Rule 9.00 of the Rules and Regulations Governing the Administration and Enforcement of the Fresh Water Wetlands Act (Rules), this project may be permitted as an **insignificant alteration** to freshwater wetlands under the following terms and conditions:

Terms and Conditions for Wetlands Application No. 15-0187 and RIPDES No. RIR101318:

1. This letter is the DEM's permit for this project under the R.I. Fresh Water Wetlands Act, Rhode Island General Laws (RIGL) Section 2-1-18 et seq. This application review has also included review related to the RIPDES "General Permit for Storm Water Discharge Associated with Construction Activity".
2. This permit is specifically limited to the project, site alterations and limits of disturbance as detailed on the site plans submitted with your application and received by the DEM on January 5, 2016. A copy of the site plans stamped approved by the DEM is enclosed. Changes or revisions to the project that would alter freshwater wetlands are not authorized without a permit from the DEM.
3. Where the terms and conditions of the permit conflict with the approved site plans, these terms and conditions shall be deemed to supersede the site plans.
4. You must notify this Program in writing immediately prior to the commencement of site alterations and upon completion of the project.

5. A copy of the stamped approved site plans and a copy of this permit must be kept at the site at all times during site preparation, construction, and final stabilization. Copies of this permit and the stamped approved plans must be made available for review by any DEM representative upon request.
6. Within ten (10) days of the receipt of this permit, you must record this permit in the land evidence records of the Towns of Middletown and Portsmouth, and supply this Program with written documentation obtained from the Towns showing this permit was recorded.
7. The effective date of this permit is the date this letter was issued. This permit expires on July 1, 2020.
8. Any material utilized in this project must be clean and free of matter that could pollute any freshwater wetland.
9. Prior to commencement of site alterations, you shall erect or post a sign resistant to the weather and at least twelve (12) inches wide and eighteen (18) inches long, which boldly identifies the initials "DEM" and the application number of this permit. This sign must be maintained at the site in a conspicuous location until such time that the project is complete.
10. Temporary erosion and sediment controls detailed or described on the approved site plans shall be properly installed at the site prior to or commensurate with site alterations. Such controls shall be properly maintained, replaced, supplemented, or modified as necessary throughout the life of this project to minimize soil erosion and to prevent sediment from being deposited in any wetlands not subject to disturbance under this permit.
11. Upon permanent stabilization of all disturbed soils, temporary erosion and/or sediment controls consisting of hay bales and/or silt fence must be removed.
12. You are responsible for the proper operation, maintenance and stability of any mitigative features, facilities, and systems of treatment and control that are installed or used in compliance with this permit to prevent harm to adjacent wetlands.
13. You are obligated to install, utilize and follow all best management practices detailed or described on the approved site plans in the construction of the project to minimize or prevent adverse impacts to any adjacent freshwater wetlands and the functions and values provided by such wetlands.
14. All plantings of shrubs, trees or other forms of vegetation as shown or detailed on the approved plans, or detailed in this permit, must be installed as soon as possible after completion of final grading; weather and season permitting. You must notify this Program in writing upon completion of the required plantings for a compliance inspection by a Program representative.
15. Buffer zone plantings of trees and/or shrubs proposed between the project and any adjacent freshwater wetland areas, except for necessary replacement, must be allowed to develop naturally without being subjected to mowing or manicuring.
16. Any plantings which fail to survive one full growing season shall be replaced. Replacement plantings shall be similarly guaranteed for one full growing season.

17. You must provide written certification from a registered land surveyor or registered professional engineer that the stormwater drainage system including any and all basins, piping systems, catch basins, culverts, swales and any other stormwater management control features have been constructed/installed in accordance with the site plans approved by this permit. This written certification must be submitted to this Program within twenty (20) days of its request or upon completion of the project.
18. This Program has made specific revisions to the approved site plans. These revisions are clearly marked highlighted in pink on the approved plans. This project must take place in compliance with these revisions. **Specifically, vegetative screen plantings have been added to the site plan at the limit of disturbance on lots 4 & 5, as shown (360 linear feet total). These plantings shall consist of mountain laurel (*Kalmia latifolia*) and/or inkberry (*Ilex glabra*), planted six (6) feet on center and four (4) feet tall after planting (see sheet C-12; sheet 12. of 18 in the plan set).**
19. Also prior to commencement of any site alterations, permanent buffer zone markers must be installed along the limit of disturbance, at the locations indicated on the approved site plans, in order to provide permanent reference points on site that are clear to present and future property owners. Acceptable permanent type markers include 4" x 4" pressure treated timber posts, galvanized fence posts with cap, or granite or concrete bounds. Markers must extend a minimum 24" above grade. A permanent-type tag or sign labeled "RIDEM Buffer Zone" must be placed on each marker. No alterations of any kind are permitted beyond these markers without first obtaining the necessary permit from this Program.
20. Immediately upon installation of the buffer zone markers, this Program must be contacted to arrange an on-site inspection. Once proper installation has been confirmed by this Program, work may be initiated on the project as herein approved.

Additionally, please be advised that this permit does not include authorization of a walking path within the "10' wide walking path easement to open space" shown on the site plan between subdivision lots 4 and 5. You must submit a new application for any new walking paths within wetlands, whether within this easement or elsewhere on site.

Pursuant to the provisions in Rule 7.09 and Rule 11.04, as applicable, any properly recorded and valid permit is automatically transferred to the new owner upon sale of the property.

Additionally, the Program has reviewed this project in accordance with the standards of the RIPDES General Permit for Storm Water Discharge Associated with Construction Activity ("CGP"). Construction Activities which disturb one (1) or more acres of land and where storm water runoff is directed, via a point source, into a separate storm sewer system or into the waters of the State, are required to seek coverage under the Rhode Island Pollutant Discharge Elimination System (RIPDES) storm water permit. Our review has determined that the project has been designed to meet the requirements of the 2013 GP. This determination therefore includes your final authorization to discharge storm water associated with construction activity under the CGP. For future references and inquiry, your permit authorization number is RIPDES No. **RIR101318**.

Both the owner and the contractor retained to undertake the construction activity are required to comply with all terms and conditions of the CGP. This includes maintaining the Soil Erosion and Sediment Control (SESC) Plan, performing the required inspections and maintenance of the selected Best Management Practices (BMPs), and retaining inspection records. Further information on the requirements of the CGP is available at:

<http://www.dem.ri.gov/pubs/regs/regs/water/ripdesca.pdf>.

Please be aware that the RIDEM's Rules and Regulations Governing the Establishment of Various Fees require that RIPDES CGP permit holders to pay an Annual Fee of \$100.00. An invoice will be sent to the owner on record in May/June of each year if the construction was still active as of December 31st of the previous year. The owner will be responsible for the Annual Fee until the construction activity has been completed, the site has been properly stabilized, and a completed Notice of Termination (NOT) has been received by the RIPDES Program. A copy of the NOT can be found attached to the CGP on the web page referenced above.

You are required to comply with the terms and conditions of this permit and to carry out this project in compliance with the Rules at all times. Failure to do so may result in an enforcement action by this Department.


In permitting the proposed alterations, the DEM assumes no responsibility for damages resulting from faulty design or construction.

Kindly be advised that this permit is not equivalent to a verification of the type or extent of freshwater wetlands on site. Should you wish to have the types and extent of freshwater wetlands verified, you may submit the appropriate application in accordance with Rule 8.03.

This permit does not remove your obligation to obtain any local, state, or federal approvals or permits required by ordinance or law and does not relieve you from any duties owed to adjacent landowners with specific reference to any changes in drainage.

Please contact Claire Swift of this office (telephone: 401-222-6820 x 7418) should you have any questions regarding this letter.

Sincerely,



Martin D. Wencek, Permitting Supervisor
Office of Water Resources
Freshwater Wetlands Program

MDW/CVS/cvs

Enclosure: Approved site plans

xc: Mohammed Freij, RIDEM OWTS Program
Traci Lima, RIPDES Program
Jack Kane, Town of Middletown Building Official
George Medeiros, Town of Portsmouth Building Official
Geraldyn E. Small, PE, Northeast Engineers & Consultants, Inc.
Scott P. Rabideau, Natural Resource Services, Inc.