

GENERAL NOTES:


1. THE LOCATION AND DEPTH OF EXISTING UTILITIES ARE APPROXIMATE AND HAVE BEEN PLOTTED FROM THE LATEST AVAILABLE INFORMATION. THE UTILITY LOCATIONS ARE APPROXIMATE AND MAY NOT BE ALL INCLUSIVE. THE CONTRACTOR SHALL CHECK AND VERIFY THE LOCATIONS OF ALL EXISTING UTILITIES, BOTH OVERHEAD AND UNDERGROUND, AND "DIG-SAFE" MUST BE NOTIFIED PRIOR TO COMMENCING ANY CONSTRUCTION OPERATIONS. RESTORATION AND REPAIR OF DAMAGE TO EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR WITH NO ADDITIONAL COST TO THE OWNER. NO EXCAVATION SHALL COMMENCE UNTIL ALL INVOLVED UTILITY COMPANIES AND/OR TOWN WHOSE FACILITIES MIGHT BE AFFECTED BY ANY WORK TO BE PERFORMED BY THE CONTRACTOR ARE NOTIFIED AT LEAST 72 HOURS IN ADVANCE.
2. THIS SITE DOES NOT LIE WITHIN ANY KNOWN AGRICULTURAL USE, SILVICULTURAL USE, NATURAL HERITAGE OR FARMLAND CONSERVATION AREAS.
3. THERE ARE NO KNOWN EASEMENTS OR RIGHTS OF WAY WITHIN OR ADJACENT TO THIS PARCEL.
4. THERE ARE NO KNOWN HISTORIC CEMETERIES WITHIN OR IMMEDIATELY ADJACENT TO THIS PARCEL.
5. WETLANDS REPORT DONE BY NATURAL RESOURCE SERVICES INC. PO BOX 311 HARRISVILLE RHODE ISLAND ON MARCH 2016.

AP 12 LOT 159
STEPHEN J. & SHERI A. BOOKER
DEED BOOK 265 PAGE 502

NO.	DATE	DESCRIPTION	BY
8	3/24/2017	AS PER DEM COMMENTS	WCR
7	1/27/2017	AS PER DEM COMMENTS	WCR
6	11/19/2016	AS PER DEM COMMENTS	WCR
5	10/10/2016	AS PER DEM COMMENTS	WCR
4	9/2/2016	LABELLED 3 BEDROOM DWELLING/ BOT. FLEYS ON ISDS SYSTEMS	WCR
3	7/29/2016	REGRADE REAR LOTS 13 & 14	WCR
2	6/28/2016	RELOCATE WELLS/ISDS SYSTEMS	WCR

LEGEND
NOT TO SCALE

	BOUNDARY
	ABUTTER
	MAJOR CONTOUR
	MINOR CONTOUR
	STONEWALL
	TREENLINE
	WETLANDS EDGE
	50' PERIMETER WETLAND
	100' RIVERBANK WETLAND
	200' RIVERBANK WETLAND
	200' ISDS HYDROLOGIC LINE
	BUILDING ENVELOPE
	LIMITS OF DISTURBANCE/ EROSION CONTROL
	ELECTRIC LINE
	SOIL EVALUATION HOLE
	IRON PIN
	BOUND
	DRILL HOLE
	PROPOSED WELL
	EXISTING UTILITY POLE
	PROPOSED LIGHT POLE



DEPARTMENT OF ENVIRONMENTAL MANAGEMENT
OFFICE OF WATER RESOURCES
OFFICE OF WETLANDS PROGRAM
FRESHWATER PLAN APPLICATION NO. 16-0179
REVIEWED BY: [Signature]
DATED: APR 6 2017
DATE OF SAME DATE

PROJECT BENCH MARK
NAIL (FND) IN POLE 21
ELEV. = 481.52
(NAVD 88 DATUM)

AP 12 LOT 135
DAVID J. & MARY E.
ARSENault
DEED BOOK 328 PAGE 223


PROPOSED DEVELOPMENT SIGN
EDGE OF PAVEMENT (TYP)

AP 12 LOT CB-42
JOEL B. KINGMAN
DEED BOOK 684 PAGE 96

Thomas J. Principe, III
No. 9107
REGISTERED PROFESSIONAL ENGINEER

NORBERT A. THERIEN
No. 1739
REGISTERED PROFESSIONAL LAND SURVEYOR

"I CERTIFY THAT THE INFORMATION SHOWN HEREON HAS BEEN OBTAINED BY AN ACTUAL SURVEY ON THE GROUND, THAT IT IS CORRECT AND THIS SURVEY AND PLAN CONFORM TO A CLASS STANDARD AS ADOPTED BY THE RHODE ISLAND BOARD OF REGISTRATION FOR PROFESSIONAL LAND SURVEYORS."
BY: [Signature]
NORBERT A. THERIEN P.L.S.




PRINCIPE COMPANY
ENGINEERING DIVISION
PO BOX 298
TIVERTON, RI 02878
401.816.5385
PRINCIPEENGINEERING@GMAIL.COM

NATIONAL
Surveyors-Developers
Inc.
42 Hamlet Ave., Woonsocket, R.I.
(401) 769-7779

" WATERVIEW ACRES "		
STEPHEN E. HOPKINS TRUSTEE		
ASSESSORS PLAT 12 LOT 134		
KEACH DAM ROAD		
GLOCESTER, RHODE ISLAND		
BOUNDARY SURVEY PLAN		
SHEET 1 OF 2		
DRAWN BY: W.C.R.	CHECKED BY: N.A.T.	FIELD BY: W.C.R.,S.K.
FEBRUARY 2015	JOB No. 2014-246	SHEET 2 OF 11

8	3/24/2017	AS PER DEM COMMENTS	WCR
7	1/27/2017	AS PER DEM COMMENTS	WCR
6	11/19/2016	AS PER DEM COMMENTS	WCR
5	10/10/2016	AS PER DEM COMMENTS	WCR
4	9/2/2016	LABELLED 3 BEDROOM DWELLING/ BOT. ELEV'S ON LOTS SYSTEMS	WCR
3	7/29/2016	REGRAVING REAR LOTS 13 & 14	WCR
2	6/28/2016	RELOCATE WELLS/SDS SYSTEMS	WCR
NO.	DATE	DESCRIPTION	BY




SCALE: 1"=40' HORIZONTAL
1"=4' VERTICAL

DEPARTMENT OF ENVIRONMENTAL MANAGEMENT
OFFICE OF WATER RESOURCES
FRESHWATER WETLANDS PROGRAM
REVIEWED SITE PLAN APPLICATION NO. 16-0179
DATED APR 06 2017
SEE LETTER OF SAME DATE.


Martin D. Wenczek

472.4	473.5	478.9	474.33	480.0	475.10	480.0	475.88	479.1	476.66	479.3	477.43	479.5	478.21	479.6	478.99	479.4	479.76	480.0	480.54	480.1	481.32	480.5	482.02	481.0	482.43	481.3	482.52	481.9	482.29	482.1	481.81	482.1	481.31	482.6	480.81	481.0	480.31	476.3	479.99	474.4	480.33	482.2	481.34	484.0	482.85	484.3	484.38	484.5	485.08	484.0	484.16	480.8
0+00		1+00		2+00		3+00		4+00		5+00		6+00		7+00		8+00		9+00		10+00		11+00		12+00		12+72.99																										



NO.	DATE	DESCRIPTION	BY
8	3/24/2017	AS PER DEM COMMENTS	WCR
7	1/27/2017	AS PER DEM COMMENTS	WCR
6	11/19/2016	AS PER DEM COMMENTS	WCR
5	10/10/2016	AS PER DEM COMMENTS	WCR
4	9/2/2016	LABELLED 3 BEDROOM DWELLING/ BOT. ELEV. ON ISDS SYSTEMS	WCR
3	7/29/2016	REGRADE REAR LOTS 13 & 14	WCR
2	6/28/2016	RELOCATE WELLS/ISDS SYSTEMS	WCR

LEGEND	
	BOUNDARY
	ABUTTER
	MAJOR CONTOUR
	MINOR CONTOUR
	STONEWALL
	TREENLINE
	WETLANDS EDGE
	50' PERIMETER WETLAND
	100' RIVERBANK WETLAND
	200' RIVERBANK WETLAND
	200' ISDS HYDROLOGIC LINE
	BUILDING ENVELOPE
	LIMITS OF DISTURBANCE/ EROSION CONTROL
	OHW
	ELECTRIC LINE
	SOIL EVALUATION HOLE
	IRON PIN
	BOUND
	DRILL HOLE
	PROPOSED WELL
	EXISTING UTILITY POLE
	PROPOSED LIGHT POLE



* NO REGRADE IN LOT AROUND PROPOSED ISDS LOCATION

DRAINAGE - SHWT SEPARATION				
LOT	FC @ DRAIN	BOY. DRAIN	SHWT EL.	SEPARATION
1	480.5	476.0	472.5	3.5'
2	480.5	476.0	470.0	6.0'
3	481.0	476.5	470.0	6.5'
4	481.0	476.5	470.0	6.5'
5	482.0	477.5	469.0	8.5'
6	482.0	477.5	473.0	4.5'
7	480.0	475.5	466.0	9.5'
8	485.0	480.5	474.0	6.5'
9	484.0	479.5	473.0	6.5'
10	482.0	477.5	474.5	3.5'
11	482.0	477.5	472.5	5.0'
12	480.0	475.5	471.0	4.5'
13	480.0	475.5	471.0	4.5'
14	482.0	477.5	472.5	5.0'
BASIN SOUTHWEST	468.0	464.0	464.0	4.0'
BASIN NORTHWEST	462.0	449.0	449.0	13.0'
BASIN EAST	484.0	473.5/488.0	473.5	10.5'

NORBERT A. THERIEN


PROFESSIONAL LAND SURVEYOR

Thomas J. Principe, III

REGISTERED PROFESSIONAL ENGINEER

"I CERTIFY THAT THE INFORMATION SHOWN HEREON HAS BEEN OBTAINED BY AN ACTUAL SURVEY ON THE GROUND, THAT IT IS CORRECT AND THIS SURVEY AND PLAN CONFORM TO A CLASS "C" STANDARD AS ADOPTED BY THE RHODE ISLAND BOARD OF REGISTRATION FOR PROFESSIONAL LAND SURVEYORS.

BY: *Norbert A. Therien*
NORBERT A. THERIEN P.L.S.



PRINCIPE COMPANY
ESTABLISHED IN 1971

PRINCIPE COMPANY, INC.
ENGINEERING DIVISION

PO BOX 298
TIVERTON, RI 02878
401.816.5385
PRINCIPEENGINEERING@GMAIL.COM

NATIONAL
Surveyors-Developers
Inc.

42 Hamlet Ave., Woonsocket, R.I.
(401) 769-7779

DEPARTMENT OF ENVIRONMENTAL MANAGEMENT
OFFICE OF WATER RESOURCES
FRESHWATER WETLANDS PROGRAM
REVIEWED SITE PLAN APPLICATION NO. 16-079
DATED APR 6 2017
SEE LETTER OF SAME DATE.

Matthew D. Wenczek

" WATERVIEW ACRES "
STEPHEN E. HOPKINS TRUSTEE
ASSESSORS PLAT 12 LOT 134
KEACH DAM ROAD
GLOCESTER, RHODE ISLAND


DRAINAGE & GRADING PLAN

DRAWN BY: W.C.R.	CHECKED BY: N.A.T.	FIELD BY: W.C.R./S.K.
FEBRUARY 2015	JOB No. 2014-246	SHEET 6 OF 11

8	3/24/2017	AS PER DEM COMMENTS	WCR
7	1/27/2017	AS PER DEM COMMENTS	WCR
6	11/19/2016	AS PER DEM COMMENTS	WCR
5	10/10/2016	AS PER DEM COMMENTS	WCR
4	9/2/2016	LABELLED BEDROOM DWELLING POLE PLAYS ON ISDS SYSTEMS	WCR
3	7/29/2016	REGRADE REAR LOTS 13 & 14	WCR
2	6/28/2016	RELOCATE WELLS/ISDS SYSTEMS	WCR
NO.	DATE	DESCRIPTION	BY

LEGEND
NOT TO SCALE

	BOUNDARY
	ABUTTER
	MAJOR CONTOUR
	MINOR CONTOUR
	STONEWALL
	TRELLINE
	WETLANDS EDGE
	50' RIVERBANK WETLAND
	100' RIVERBANK WETLAND
	200' RIVERBANK WETLAND
	200' ISDS HYDROLOGIC LINE
	BUILDING ENVELOPE
	LIMITS OF DISTURBANCE/ EROSION CONTROL
	OHW
	ELECTRIC LINE
	SOIL EVALUATION HOLE
	IRON PIN
	BOUND
	DRILL HOLE
	PROPOSED WELL
	EXISTING UTILITY POLE
	PROPOSED LIGHT POLE



WOODED AREA

CART PATH (TYP)

LOW 462

KEACH DAM ROAD

DAM

EXISTING BITUMINOUS PAVED ENTRANCE TO BE REMOVED



EDGE OF PAVEMENT (TYP)

PROJECT BENCH MARK
NAIL (FND) IN POLE 21
ELEV. = 481.52
(NAVD 88 DATUM)


PROPOSED SOIL & EROSION CONTROL FENCE/TRENCH

DEPARTMENT OF ENVIRONMENTAL MANAGEMENT
OFFICE OF WATER RESOURCES
FRESHWATER WETLANDS PROGRAM
REVIEWED SITE PLAN APPLICATION NO. 16-0129
DATED APR 06 2017
SEE LETTER OF SAME DATE.

Stephen E. Hopkins
" WATERSHED ACRES "
STEPHEN E. HOPKINS TRUSTEE
ASSESSORS PLAT 12 LOT 134
KEACH DAM ROAD
GLOCESTER, RHODE ISLAND
DRAINAGE & GRADING PLAN
PRE-WATERSHED



"I CERTIFY THAT THE INFORMATION SHOWN HEREON HAS BEEN OBTAINED BY AN ACTUAL SURVEY ON THE GROUND, THAT IT IS CORRECT AND THIS SURVEY AND PLAN CONFORM TO A CLASS 2 STANDARD AS ADOPTED BY THE RHODE ISLAND BOARD OF REGISTRATION FOR PROFESSIONAL LAND SURVEYORS."
BY: *Norbert A. Therien*
NORBERT A. THERIEN P.L.S.




PRINCIPE COMPANY
PRINCIPE COMPANY, INC.
ENGINEERING DIVISION
PO BOX 298
TIVERTON, RI 02878
401.816.5385
PRINCIPEENGINEERING@GMAIL.COM


NATIONAL
Surveyors-Developers
Inc.
42 Hamlet Ave., Woonsocket, R.I.
(401) 789-7779

DRAWN BY: W.C.R. CHECKED BY: N.A.T. FIELD BY: W.C.R., S.K.
FEBRUARY 2015 JOB No. 2014-246 SHEET 7 OF 11

8	3/24/2017	AS PER DEM COMMENTS	WCR
7	1/27/2017	AS PER DEM COMMENTS	WCR
6	11/19/2016	AS PER DEM COMMENTS	WCR
5	10/10/2016	AS PER DEM COMMENTS	WCR
4	9/2/2016	LABELLED 3 BEDROOM DWELLING/ BOT. ELEV'S ON SDS SYSTEMS	WCR
3	7/29/2016	REGRADE REAR LOTS 13 & 14	WCR
2	6/28/2016	RELOCATE WELLS/SDS SYSTEMS	WCR
NO.	DATE	DESCRIPTION	BY




NDS POP-UP DRAINAGE EMITTER
NOT TO SCALE



ROOF LEADER COLLECTOR DETAIL
NOT TO SCALE

DEPARTMENT OF ENVIRONMENTAL MANAGEMENT
OFFICE OF WATER RESOURCES
FRESHWATER WETLANDS PROGRAM
REVIEWED SITE PLAN APPLICATION NO. 16-0179
DATED APR 06 2017
SEE LETTER OF SAME DATE.




RECOMMENDED MINIMUM TRENCH WIDTH

PIPE DIAMETER IN. (MM)	TRENCH WIDTH IN. (M)
4 - 8 (100-200)	*
10 (250)	24 (0.6)
12 (300)	28 (0.7)
15 (375)	35 (0.9)
18 (450)	43 (1.1)
24 (600)	56 (1.4)
30 (750)	60 (1.5)
36 (900)	65 (1.7)
42 (1050)	84 (2.1)
48 (1200)	91 (2.3)
54 (1350)	97 (2.5)
60 (1500)	103 (2.6)

* USUALLY BASED ON SMALLEST BUCKET SIZE AVAILABLE.


REFERENCE ASTM D2321, "STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF THERMOPLASTIC PIPE FOR SEWERS AND OTHER GRAVITY-FLOW APPLICATIONS."



PIPE DIAMETER (INCHES)


DIAMETER	10/12	15	18	24	30	36
A	42	41	49	59.5	88	88
B	14.5	19	22	28	36	43
C	33	34	43	48	63.5	66.5
D	6	6	6	6	6	6

HDPE PIPE END FLARED END SECTION
NOT TO SCALE



INFILTRATION BASIN CROSS SECTION DETAIL
NOT TO SCALE

INFILTRATION BASIN NOTES:
1) DURING CONSTRUCTION HEAVY EQUIPMENT SHALL NOT TRAVERSE THE INFILTRATION AREA IN ORDER TO PREVENT DETRIMENTAL COMPACTION.
2) SHOP DRAWING SUBMITTAL AND APPROVAL BY DESIGN ENGINEER REQUIRED FOR EACH INFILTRATION BASIN PRIOR TO CONSTRUCTION.



ROCK FILL RIP-RAP
© FLARED END SECTIONS
NOT TO SCALE

NOTES:
1. CLASS OF RIP-RAP AND BEDDING TO BE SPECIFIED IN CONTRACT DOCUMENTS.
2. DIMENSIONS MAY BE MODIFIED BY ENGINEER TO MEET FIELD CONDITIONS.
3. UNLESS OTHERWISE SPECIFIED, DUMPED RIP-RAP SHALL BE USED.





TABLE 1
CATCH BASIN DIMENSIONS (IN)

DIAMETER (D)	W	L	MIN. COVER
4'-0"	3'-0"	5'-0"	12"
5'-0"	4'-0"	6'-0"	18"
6'-0"	5'-0"	7'-0"	24"

FOR ADDITIONAL (VERTICAL STAGERS) REQUIREMENTS REFER TO ASTM C940, USN 6.1.2



NOTES:
1. SHALL BE IN ACCORDANCE WITH SECTION 702 OF THE R.I. STANDARD SPECIFICATIONS.
2. ANY NECESSARY ADJUSTMENTS DURING CONSTRUCTION WILL BE DONE BY SAW-CUTTING AND/OR CORING ONLY. NO JACKHAMMERS, HAMMERS AND CHISELS OR PNEUMATIC TOOLS WILL BE ALLOWED.
3. THE CENTER LINE OF THE OPENING MUST BE WITHIN 2" FROM THE STEPS.
4. ALTERNATE TOP COVER IS STEEL REINFORCED TO MEET OR EXCEED H-25 OR HS-25 LOADINGS WITH EARTH PRESSURES INCLUDED. THIS IMPLIES THAT THE TOP SLAB IS DESIGNED FOR AXLE LOADS OF NO MORE THAN 20 TONS.
5. ALL REBAR SHALL HAVE A MINIMUM OF 2" CLEARANCE FROM OPENING.
6. ALL REBAR IN THE BOTTOM MAT ARE #5 @ 21" BOTH WAYS, WITH 2" MINIMUM COVER, EXCEPT FOR REBAR ADJACENT TO THE OPENING. THESE BARS SHALL BE (3)-#6 SHOWN WITH A HEAVIER LINE FOR CLARITY. REBAR IN THE TOP MAT ARE #5 @ 1'-0" BOTH WAYS, WITH 2" MINIMUM COVER, EXCEPT FOR REBAR ADJACENT TO THE OPENING. THESE BARS SHALL BE (2)-#6 BARS.


RHODE ISLAND DEPARTMENT OF TRANSPORTATION

ALTERNATE TOP COVER FOR ROUND PRECAST MANHOLES AND CATCH BASINS

REVISIONS

NO.	BY	DATE
1	JLP	7/21/08

R.I. STANDARD 4.7.2




RHODE ISLAND DEPARTMENT OF TRANSPORTATION

SQUARE FRAME AND GRATE (BICYCLE SAFE)

REVISIONS

NO.	BY	DATE
1	JLP	7/21/08

R.I. STANDARD 6.3.2



ITEM NUMBER	B	BB	X	Y	FRAME
24643-SQH	59-7/8	25-1/4		2	4-SIDED
24644-SQH	59-7/8	32-3/4		2	4-SIDED
24653-SQH	59-7/8	28-1/4		2	3-SIDED
24654-SQH	59-7/8	32-3/4		2	4-SIDED
24655-SQH	59-7/8	28-1/4		2	3-SIDED
24656-SQH	59-7/8	32-3/4		2	4-SIDED

Thomas J. Principe, III
No. 9107
REGISTERED PROFESSIONAL ENGINEER

PRINCE COMPANY, INC.
ENGINEERING DIVISION
P.O. BOX 298
TIVERTON, RI 02878
401.816.5385
PRINCEENGINEERING@GMAIL.COM

REVISIONS

No.	DATE	DRWN	CHKD
-----	------	------	------

KEACH DAM ROAD
GLOCESTER, RHODE ISLAND
DETAIL SHEET-1

SCALE: NTS

SHEET NO: 9 OF 11

DRAWN BY: TJP DESIGN BY: SL CHECKED BY: TJP

DATE: 3/10/16 PROJECT NO.: LD_2016_245

EROSION CONTROL, SOIL STABILIZATION AND SEDIMENT CONTROL PLAN

- PRIOR TO THE COMMENCEMENT OF ANY CLEARING, GRUBBING, DEMOLITION OR EARTHWORK ACTIVITY, TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES AS INDICATED ON THE PLANS ARE TO BE INSTALLED BY THE CONTRACTOR.
- CONSTRUCTION ACCESS STABILIZATION ENTRANCE PADS ARE TO BE INSTALLED PRIOR TO THE COMMENCEMENT OF SITE GRUBBING OR EARTHWORK ACTIVITY.
- EXISTING CATCH BASINS ARE TO BE PROTECTED WITH HAY BALES AND/OR SILT SACS PRIOR TO THE START OF SITE GRUBBING, EARTHWORK OR UNDERGROUND UTILITY AND DRAINAGE INFRASTRUCTURE INSTALLATION TO SERVE THE DEVELOPMENT SITE.
- THE PROJECT CONSTRUCTION SEQUENCE, TO THE EXTENT PRACTICAL, SHOULD REQUIRE THE INSTALLATION OF DOWN GRADE AND OFF SITE STORM DRAINAGE SYSTEM IMPROVEMENTS BEFORE THE START OF SITE GRUBBING AND EARTHWORK ACTIVITY.
- TEMPORARY SITE SLOPE TREATMENTS FOR SOIL STABILIZATION SHALL CONSIST OF HAY, STRAW, FIBER MULCH, RIP RAP OR PROTECTIVE COVERS SUCH AS MAT OR FIBER LINING (BURLAP, JUTE, FIBERGLASS NETTING, AND EXCELSIOR OR EQUAL PRODUCTS). THESE AND OTHER ACCEPTABLE MEASURES SHALL BE INCORPORATED INTO THE SITE WORK AS WARRANTED OR AS ORDERED BY THE ENGINEER.
- CONSTRUCTION SITES ARE DYNAMIC, THE CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND OR MOVEMENT AND MAINTENANCE OF EROSION CONTROLS, SOIL STABILIZATION AND SEDIMENT CONTROL MEASURES AS NEEDED TO MAXIMIZE THE INTENT OF THE PLAN FOR ALL SITE CONDITIONS THROUGHOUT THE CONSTRUCTION PERIOD.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PERIODIC INSPECTION, MAINTENANCE, REPAIR, AND REPLACEMENT OF EROSION CONTROLS, SOIL STABILIZATION AND SEDIMENT CONTROL DEVICES UNTIL AN ACCEPTABLE PERMANENT VEGETATIVE GROWTH IS ESTABLISHED. THE CONTRACTOR SHALL MAINTAIN A DETAIL LOG OF ALL EROSION CONTROL INSPECTIONS, COMPLAINTS RELATED TO EROSION OR SEDIMENT, AND CORRECTIVE REMEDIAL MEASURES TAKEN THROUGHOUT THE COURSE OF THE PROJECT CONSTRUCTION.
- SOIL EROSION AND SEDIMENT CONTROL IS NOT LIMITED TO DAMAGES CAUSED BY WATER BUT ALSO INCLUDES EROSION AND SEDIMENT RESULTING FROM WINDS. MEASURES, SUCH AS TEMPORARY GROUND COVERS, WATER AND CALCIUM APPLICATIONS ARE TO BE UNDERTAKEN AS NEEDED TO MINIMIZE WIND RELATED SOIL AND DUST CONTROL.
- STOCK PILES OF EARTH MATERIALS SHALL NOT BE LOCATED NEAR WATERWAYS OR WETLANDS. STOCK PILES SHALL HAVE SIDE SLOPES NO GREATER THAN THIRTY PERCENT (30%). STOCK PILES SHALL BE SURROUNDED ON THE DOWN GRADIENT OF THE EXISTING GROUND SURFACE BY HAY BALES OR SILT FENCE. THE STOCK PILES SHALL ALSO BE SEEDED OR STABILIZED IN SOME MANNER TO PREVENT SOIL EROSION.
- THE SMALLEST POSSIBLE SITE AREAS SHALL BE DISTURBED OR EXPOSED AT ONE TIME AND DENUDED SLOPES OR WORK AREAS SHALL NOT BE LEFT EXPOSED FOR EXCESSIVE PERIODS OF TIME, SUCH AS INACTIVE PERIODS OR SITE WORK SHUT DOWNS.
- TO THE EXTENT POSSIBLE, ALL DISTURBED AREAS MUST BE SEEDED OR STABILIZED WITHIN THE CONSTRUCTION SEASON. STABILIZATION OF ONE FORM OR ANOTHER SHALL BE ACHIEVED WITHIN FIFTEEN (15) DAYS OF FINAL GRADING.
- EXPOSED STEEP OR LONG SLOPES SHOULD BE TREATED WITH "CRIMPING" OR "TRACKING" TO REDUCE EROSION AND SEDIMENT AND TO TACK DOWN SEEDING OR MULCH APPLICATIONS.
- IF CONCRETE IS TO BE USED ON SITE, THE CONTRACTOR MUST ESTABLISH AND MAINTAIN SPECIFIC WASHOUT AREAS FOR THE CONCRETE TRUCKS WITH APPROPRIATE PROTECTION CONTROLS.
- THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING AND MAINTAINING COLLECTION AND STORAGE LOCATIONS ON-SITE FOR ALL CONSTRUCTION DEBRIS AND TRASH SO THAT THIS MATERIAL DOES NOT BECOME A NEIGHBORHOOD NUISANCE.
- EXISTING TREES AND VEGETATION WILL BE RETAINED WHENEVER FEASIBLE.
- SITE SOIL EROSION AND SOIL STABILIZATION AND SEDIMENT CONTROLS MUST CONFORM TO ALL REQUIREMENTS OF THE APPLICABLE LOCAL COMMUNITY ORDINANCES AND STATE REGULATIONS.

VEGETATIVE COVER AND PLANTING

- THE NORMAL ACCEPTABLE SEASONABLE SEEDING DATES ARE APRIL 1ST THROUGH OCTOBER 15TH.
- TOP SOIL FOR PERMANENT OR LONG TERM TEMPORARY SEEDING SHOULD HAVE A SANDY LOAM TEXTURE, RELATIVELY FREE OF SUBSOIL MATERIAL, STONES, ROOTS, LUMPS OF SOIL, TREE LIMBS, TRASH OR CONSTRUCTION DEBRIS. TOP SOIL SHALL CONFORM WITH RHODE ISLAND SPECIFICATIONS M18.01.
- THE DESIGN SEED MIX UTILIZED IN ALL DISTURBED AREAS TO BE SEEDED SHALL BE COMPRISED OF THE FOLLOWING:

TYPE	% BY WEIGHT	SEEDING DATE
CREeping RED FESCUE	70	APRIL 1 - JUNE 15
ASTORIA BENTGRASS	5	
BIRDFOOT TREFOIL	15	AUGUST 15 - OCTOBER 15
PERENNIAL RYE GRASS	10	

APPLICATION RATE - 100 LBS PER ACRE

SEED MIX SHALL BE INOCULATED WITHIN 24 - HOURS BEFORE MIXING AND PLANTING, WITH APPROPRIATE INOCULATION FOR EACH SEED VARIETY. ALTERNATE SEED TYPES DUE TO SITE SPECIFIC CONDITIONS AND SOILS ARE ACCEPTABLE WITH THE ENGINEER'S APPROVAL.
- IN TOPSOIL SEEDING AREAS, THE CONTRACTOR WILL LIME AND FERTILIZE AS REQUIRED TO COMPLIMENT OR UPGRADE SOIL CONDITIONS.
- THE CONTRACTOR MUST REPAIR AND/OR RESEED ANY PERMANENT VEGETATIVE COVER AREAS THAT DO NOT DEVELOP OR WHICH ERODE WITHIN A ONE (1) YEAR PERIOD.

GENERAL NOTES:

- IT SHALL BE THE CONTRACTOR'S SOLE RESPONSIBILITY TO FAMILIARIZE HIMSELF WITH ANY APPLICABLE LOCAL, STATE AND FEDERAL LAWS GOVERNING HIS INTENDED ACTIVITIES. OSHA REGULATIONS ARE APPLICABLE OF PROJECT SITE CONSTRUCTION ACTIVITIES.
- ALL CONSTRUCTION WILL BE UNDERTAKEN IN ACCORDANCE WITH THE APPLICABLE REQUIREMENTS OF THE TOWN OF SCITUATE.
- IT SHALL BE THE CONTRACTOR'S SOLE RESPONSIBILITY TO MAINTAIN THE INTEGRITY OF ALL EXISTING UTILITIES, STRUCTURES, AND ABUTTING PROPERTIES. THE COST OF ANY REPAIR OR REPLACEMENT OF DAMAGED ITEMS SHALL BE BORNE BY THE CONTRACTOR.
- IF THE MUNICIPALITY REQUIRES A PROJECT PRE-CONSTRUCTION CONFERENCE, THE PROJECT DEVELOPER AND THE PROJECT CONTRACTOR WILL ATTEND AND WILL PROVIDE ALL REQUESTED MATERIALS PRIOR TO COMMENCING ANY WORK.
- IF CEMENT CONCRETE MIX TRUCKS ARE TO BE WASHED OUT ON SITE, THE CONTRACTOR IS RESPONSIBLE FOR ESTABLISHING AND MAINTAINING A WASH OUT AREA WITH APPROPRIATE PROTECTION CONTROLS.
- THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING AND MAINTAINING COLLECTION AND STORAGE LOCATIONS ON-SITE FOR ALL CONSTRUCTION DEBRIS AND TRASH SO THAT THIS MATERIAL DOES NOT BECOME A NEIGHBORHOOD NUISANCE.


- ALL REQUIRED SITE IMPROVEMENTS SHALL BE INSPECTED BY THE TOWN ENGINEER TO ENSURE SATISFACTORY COMPLETION. IN NO CASE SHALL THE INSTALLATION OF ANY IMPROVEMENTS BE STARTED UNTIL PRIOR NOTIFICATION IS GIVEN TO THE TOWN ENGINEER. AT LEAST A 48-HOUR NOTICE SHALL BE GIVEN TO THE TOWN ENGINEER PRIOR TO ANY SUCH START OF CONSTRUCTION. A FINAL INSPECTION OF ALL SITE IMPROVEMENTS, UTILITIES AND GRADING WILL BE MADE TO DETERMINE WHETHER THE WORK IS SATISFACTORY AND IN SUBSTANTIAL AGREEMENT WITH THE APPROVED FINAL CONSTRUCTION DRAWING AND THE TOWN SPECIFICATIONS.
- LOCATION AND DEPTH OF EXISTING UTILITIES ARE APPROXIMATE AND HAVE BEEN PLOTTED FROM THE BEST AVAILABLE INFORMATION. THE CONTRACTOR SHALL CHECK AND VERIFY LOCATIONS OF ALL EXISTING UTILITIES BOTH UNDERGROUND AND OVERHEAD. ANY DAMAGE TO EXISTING UTILITIES AS SHOWN OR NOT SHOWN ON THE PLANS SHALL BE THE CONTRACTOR'S RESPONSIBILITY. COSTS OF SUCH DAMAGE SHALL BE BORNE BY THE CONTRACTOR. NO EXCAVATION SHALL BE DONE UNTIL ALL INVOLVED UTILITY COMPANIES ARE NOTIFIED 48-HOURS IN ADVANCE. THE CONTRACTOR SHALL BE RESPONSIBLE TO NOTIFY DIG-SAFE (1-800-344-7233) A MINIMUM OF 48 WORKING HOURS, EXCLUDING WEEKENDS AND HOLIDAYS, PRIOR TO THE START OF ANY EXCAVATION AND/OR BLASTING WORK. THE NAME OF THE COMPANY PERFORMING THE EXCAVATION AND/OR BLASTING WORK MUST BE SUPPLIED TO DIG-SAFE, IF IT IS DIFFERENT FROM THE CALLER.
- IT SHALL BE THE CONTRACTOR'S SOLE RESPONSIBILITY TO OBTAIN ANY AND ALL PERMITS REQUIRED BY, BUT NOT LIMITED TO, THE STATE OF RHODE ISLAND AND ALL INDIVIDUAL UTILITY COMPANIES PRIOR TO COMMENCING ANY WORK.
- ALL MATERIAL FOR FILL SHALL BE CLEAN AND FREE OF MATTER WHICH COULD POLLUTE ANY DOWN STREAM WATERCOURSE.
- FILL MATERIAL SHALL BE COMPACTED IN ONE FOOT (MAXIMUM) LIFTS TO AT LEAST 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED IN ACCORDANCE WITH ASTM D-1557 (MODIFIED PROCTOR TEST).

THE FOLLOWING LIST OF MAINTENANCE TASKS AND FREQUENCIES MUST BE ADHERED TO IN ORDER TO INSURE A SUCCESSFUL LONG TERM OPERATION OF THE STORM DRAINAGE SYSTEM.

- DURING CONSTRUCTION ACTIVITIES ALL EROSION CONTROLS ON THE SITE SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN (7) CALENDAR DAYS AND WITHIN TWENTY FOUR (24) HOURS AFTER AN EVENT WHICH GENERATES AT LEAST 0.25 INCHES OF RAIN IN A TWENTY FOUR (24) HOUR PERIOD.
- SEDIMENTS SHALL BE REMOVED FROM ALL BASINS IMMEDIATELY AFTER SITE STABILIZATION.
- ALL TRASH, LITTER AND OTHER DEBRIS SHALL BE REMOVED FROM ALL STORM WATER INLET AND OUTLET STRUCTURES A MINIMUM OF TWICE PER YEAR. THESE STRUCTURES SHALL ALSO BE INSPECTED TWICE PER YEAR. INSPECTIONS SHALL BE PERFORMED SEVERAL TIMES WITHIN THE FIRST SIX MONTHS OF OPERATION.
- INSPECTIONS OF ALL CATCH BASINS SHALL OCCUR ON AN ANNUAL BASIS TO CHECK FOR DEBRIS REMOVAL (SEDIMENT AND HYDROCARBONS) AND STRUCTURAL INTEGRITY OR DAMAGE. SUCH DEFICIENCIES SHALL BE CORRECTED IMMEDIATELY.
- REPAIRS OR REPLACEMENT OF INLET/OUTLET STRUCTURES OR ANY ELEMENT OF THE FACILITY SHALL BE DONE WITHIN THIRTY (30) DAYS OF DEFICIENCY REPORTS. IF AN EMERGENCY SITUATION IS IMMINENT THEN REPAIR/REPLACEMENT SHALL BE DONE IMMEDIATELY TO AVERT FAILURE OR DANGER TO NEARBY RESIDENTS.
- MAKE REPAIRS IMMEDIATELY USING APPROPRIATE STONE SIZES. DO NOT PLACE STONES ABOVE FINISHED GRADE.
- ALL REMOVED SEDIMENTS AND DEBRIS SHALL BE DISPOSED OF OFF SITE IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS.
- ALL OUTLET STRUCTURES AND OUTFLOW CHANNELS WILL BE INSPECTED ANNUALLY. INSPECTIONS WILL BE ACCOMPLISHED SEVERAL TIMES DURING THE FIRST SIX MONTHS OF OPERATION, ESPECIALLY AFTER RAINFALL EVENTS TO CHECK FOR CLOGGING OR, CONVERSELY, TOO RAPID OF A RELEASE.
- REPAIRS OR REPLACEMENT OF INLET/OUTLET STRUCTURES, RIP-RAP CHANNELS, FENCES, OR OTHER ELEMENTS OF THE FACILITY WILL BE DONE WITHIN 30 DAYS OF DEFICIENCY REPORTS. IF AN EMERGENCY SITUATION IS IMMINENT THEN REPAIR/REPLACEMENT MUST BE DONE IMMEDIATELY TO AVERT FAILURE OR DANGER TO NEARBY RESIDENTS.
- ALL SEDIMENT GENERATED DURING CONSTRUCTION AND AS A RESULT OF MAINTENANCE OF THE DRAINAGE SYSTEM MUST BE DISPOSED OF PROPERLY. SEDIMENT SHALL NOT BE DISPOSED OF IN OR NEAR STATE OR FEDERAL REGULATED WATERS.
- ADDITIONAL BMP INSPECTION/MAINTENANCE MEASURES OUTLINED WITHIN THE PROJECT STORMWATER POLLUTION PREVENTION PLAN SHALL BE ADHERED TO.

DRAINAGE AND UTILITY NOTES:


- UTILITY LOCATION VERIFICATION IS TO INCLUDE TEST HOLES AS NEEDED.
- UNDERGROUND UTILITIES, ELECTRIC, TELEPHONE, FIRE ALARM CABLE, TELEVISION AND GAS SERVICES SHALL BE INSTALLED PER THE REQUIREMENTS OF THE APPLICABLE SITE UTILITY PROVIDER
- METALLIC WARNING TAPE SHALL BE INSTALLED 12" ABOVE ALL STORM DRAIN AND OTHER UTILITIES.
- IT SHALL BE THE CONTRACTOR'S SOLE RESPONSIBILITY TO MAINTAIN THE INTEGRITY OF ALL EXISTING UTILITIES, STRUCTURES AND ABUTTING PROPERTIES. THE COST OF ANY REPAIR OR REPLACEMENT OF DAMAGED ITEMS SHALL BE BORNE BY THE CONTRACTOR.



STOCKPILE DETAIL
NOT TO SCALE


MAINTENANCE NOTES:

- Maintenance responsibility for a basin and its setback shall be vested with a responsible authority by means of a legally binding and enforceable maintenance agreement that is executed as a condition of plan approval.
 - The principal spillway shall be equipped with a removable trash rack, and generally accessible from dry land.
 - A maintenance right-of-way or easement shall extend to a basin from a public or private road.
 - Sediment shall be removed from stormwater basins when the sediment volume exceeds 10% of the total basin volume and should be disposed of according to an approved comprehensive operation and maintenance plan.
- Annual mowing of the basin setback is only required along maintenance rights-of-way and the embankment. The remaining setback can be managed as rangeland (mowing every other year) or forest.




Grassed Swale Cross Section
NOT TO SCALE

NO.	DATE	DESCRIPTION	BY
8	3/24/2017	AS PER DEM COMMENTS	WCR
7	1/27/2017	AS PER DEM COMMENTS	WCR
6	11/19/2016	AS PER DEM COMMENTS	WCR
5	10/10/2016	AS PER DEM COMMENTS	WCR
4	9/9/2016	LABELLED BOTTOM DIMENSIONS/ BOT. ELEV'S ON ISDS SYSTEMS	WCR
3	7/29/2016	REGRADE REAR LOTS 13 & 14	WCR
2	6/28/2016	RELOCATE WELLS/ISDS SYSTEMS	WCR



SILK SOCK INSTALLATION
NOT TO SCALE



NOTE: SHALL BE IN ACCORDANCE WITH SECTION 211 OF THE R.I. STANDARD SPECIFICATIONS.

REVISIONS		NO. BY DATE	

RHODE ISLAND DEPARTMENT OF TRANSPORTATION
CONSTRUCTION ACCESS
JUNE 15, 1998
R.I. STANDARD 9.9.0

Thomas J. Principe, III
No. 9107
REGISTERED PROFESSIONAL ENGINEER

PRINCIPE COMPANY, INC.
ENGINEERING DIVISION
PO BOX 295
TIVERTON, RI 02878
401.816.5385
PRINCIPEENGINEERING@GMAIL.COM

DEPARTMENT OF ENVIRONMENTAL MANAGEMENT
OFFICE OF WATER RESOURCES
FRESHWATER WETLANDS PROGRAM
REVIEWED SITE PLAN APPLICATION NO. 16-0179
DATED APR 06 2017
SEE LETTER OF SAME DATE.

REVISIONS

No.	DATE	DRWN	CHKD

KEACH DAM ROAD
GLOCESTER, RHODE ISLAND
DETAIL SHEET-2


SCALE: NTS	SHEET NO: 10 OF 11
DRAWN BY: TJP	DESIGN BY: SL
DATE: 3/10/16	CHECKED BY: TJP
PROJECT NO.: LD_2016_245	

CULTEC RECHARGER 330 SPECIFICATIONS

GENERAL
CULTEC RECHARGER 330 CHAMBERS ARE DESIGNED FOR UNDERGROUND STORMWATER AND/OR ON-SITE WASTEWATER MANAGEMENT. THE CHAMBERS MAY BE USED FOR RETENTION, RECHARGING, DETENTION, CONTROLLING THE FLOW OF ON-SITE STORMWATER RUNOFF OR AS SEPTIC LEACHFIELDS.







CHAMBER PROPERTIES

- THE CHAMBERS WILL BE MANUFACTURED BY CULTEC, INC. BROOKFIELD, CT (203-775-4416).
- CONTACT CULTEC, INC. AT 203-775-4416 FOR SUBMITTAL PACKAGES AND TO PURCHASE PRODUCT.
- THE NOMINAL CHAMBER DIMENSIONS OF THE CULTEC RECHARGER 330 SHALL BE 30.5 INCHES TALL, 52 INCHES WIDE AND 7.5 FEET LONG. THE INSTALLED LENGTH OF INTERMEDIATE UNITS SHALL BE 6.25 FEET.
- THE STANDARD-DUTY VERSION OF THE CHAMBER COMES STANDARD WITH A 4.75 INCH INLET/OUTLET. MAXIMUM INLET OPENING IS 24 INCHES.
- THE HEAVY-DUTY CHAMBER WILL HAVE 15 CORRUGATIONS THE STANDARD-DUTY CHAMBER WILL HAVE 14 CORRUGATIONS.
- THE NOMINAL STORAGE VOLUME OF THE RECHARGER 330HD WILL BE 7.459 CUF/F.
- THE CHAMBERS WILL BE VACUUM THERMOFORMED OF BLACK HIGH MOLECULAR WEIGHT HIGH DENSITY POLYETHYLENE (HMWHDPE) IN AN ISO-9001:2000 CERTIFIED FACILITY.
- CHAMBERS ARE MANUFACTURED WITH AN OPEN BOTTOM, INTEGRALLY FORMED END WALLS AND PERFORATED SIDEWALLS.
- THE CHAMBERS WILL BE JOINED USING AN INTERLOCKING OVERLAPPING RIB METHOD. CONNECTIONS MUST BE FULLY SHOULDERED OVERLAPPING RIBS, HAVING NO SEPARATE COUPLINGS OR SEPARATE END WALLS.
- THE CHAMBER'S END WALL WILL BE AN INTEGRAL PART OF THE CONTINUOUSLY FORMED UNIT. SEPARATE INLET OR END PLATES CANNOT BE USED WITH THIS UNIT.
- THE RECHARGER 330R STAND-ALONE UNIT MUST BE FORMED AS A WHOLE CHAMBER HAVING TWO FULLY FORMED INTEGRAL END WALLS.
- THE RECHARGER 330S STARTER CHAMBER MUST BE FORMED AS A WHOLE CHAMBER HAVING ONE FULLY FORMED INTEGRAL END WALL AND ONE PARTIALLY FORMED INTEGRAL ENDWALL WITH A LOWER TRANSFER OPENING OF 10.5 INCHES HIGH X 40.5 INCHES WIDE.
- THE RECHARGER 330I INTERMEDIATE CHAMBER MUST BE FORMED AS A WHOLE CHAMBER HAVING AT LEAST ONE FULLY FORMED INTEGRAL END WALL AND ONE PARTIALLY FORMED INTEGRAL ENDWALL WITH A LOWER TRANSFER OPENING OF 10.5 INCHES HIGH X 40.5 INCHES WIDE.
- THE RECHARGER 330E END CHAMBER MUST BE FORMED AS A WHOLE CHAMBER HAVING ONE FULLY FORMED INTEGRAL END WALL.
- ALL CHAMBERS WILL BE ARCHED IN SHAPE. THE HEAVY DUTY CHAMBER WILL HAVE SEVENTY-EIGHT 3/4 INCH ROUND DISCHARGE HOLES. THE STANDARD-DUTY CHAMBER WILL HAVE SEVENTY-TWO 3/4 INCH ROUND DISCHARGE HOLES BORED INTO THE SIDEWALLS OF THE UNITS CORE TO PROMOTE INFILTRATION/EXFILTRATION.
- CHAMBERS MUST HAVE HORIZONTAL STIFFENING FLEX REDUCTION STEPS BETWEEN THE RIBS.
- RECHARGER 330HD HEAVY-DUTY CHAMBERS ARE DESIGNED TO WITHSTAND AASHTO H-20 LOAD RATING (32,000 LBS AXLE) WHEN INSTALLED ACCORDING TO CULTEC'S MOST CURRENT INSTALLATION INSTRUCTIONS. RECHARGER 330HD HEAVY-DUTY UNITS ARE DESIGNATED BY A COLORED STRIPE FORMED INTO THE PART ALONG THE LENGTH OF THE CHAMBER.
- RECHARGER 330 STANDARD-DUTY CHAMBERS ARE DESIGNED TO WITHSTAND AASHTO H-10 LOAD RATING (16,000 LBS AXLE) WHEN INSTALLED ACCORDING TO CULTEC'S MOST CURRENT INSTALLATION INSTRUCTIONS.
- POLYETHYLENE CHAMBERS MUST HAVE THE ABILITY TO ACCEPT AND CARRY PIPE THROUGH ITS INTEGRALLY FORMED VERTICAL SUPPORT WALL WITHOUT THE USE OF SEPARATE PIPE HANGERS.
- UNITS WILL HAVE A RAISED INTEGRAL CAP AT THE TOP OF THE ARCH IN THE CENTER OF EACH UNIT TO BE USED AS AN OPTIONAL INSPECTION PORT OR CLEAN-OUT.
- THE UNITS MAY BE TRIMMED TO CUSTOM LENGTHS BY CUTTING BACK TO ANY CORRUGATION.
- REPEATING SUPPORT PANELS AND END WALLS OF THE ELONGATED CHAMBER SHALL BE SPACED EVERY 6.25 FEET.



11.32 CUBIC FEET OF STORAGE PER LINEAL FOOT INSTALLED ACCORDING TO DESIGN UNIT

* NOTE: ALTHOUGH NOT A STANDARD PRACTICE, ONE INSPECTION PORT PER SYSTEM WILL BE INSTALLED, AS REQUESTED.




**7.459 CUBIC FEET OF STORAGE PER LINEAL FOOT
46.62 CUBIC FEET OF STORAGE PER CHAMBER INSTALLED LENGTH**



Concrete Pipe Division

**STC 900 Precast Concrete Stormceptor®
(900 U.S. Gallon Capacity)**



Section Thru Chamber

* TO BE INSTALLED @ DCB-2 & DCB-4

Notes:

- The Use Of Flexible Connection is Recommended at The Inlet and Outlet Where Applicable.
- The Cover Should be Positioned Over The Outlet Drop Pipe and The Oil Port.
- The Stormceptor System is protected by one or more of the following U.S. Patents: #4085146, #5498331, #5725760, #5753115, #5849181, #6068765, #6371690.
- Contact a Concrete Pipe Division representative for further details not listed on this drawing.

DEPARTMENT OF ENVIRONMENTAL MANAGEMENT
OFFICE OF WATER RESOURCES
FRESHWATER WETLANDS PROGRAM
REVIEWED SITE PLAN APPLICATION NO.: 16-0179
DATED APR 06 2017
SEE LETTER OF SAME DATE.


Martin D. Wencik

NO.	DATE	DESCRIPTION	BY
8	3/24/2017	AS PER DEM COMMENTS	WCR
7	1/27/2017	AS PER DEM COMMENTS	WCR
6	11/19/2016	AS PER DEM COMMENTS	WCR
5	10/10/2016	AS PER DEM COMMENTS	WCR
4	9/2/2016	LABELED 3-STEP DOWN THE SLOPE BOT. ELEV. ON ISDS SYSTEMS	WCR
3	7/29/2016	REGRADING REAR LOTS 13 & 14	WCR
2	6/28/2016	RELOCATE WELLS/ISDS SYSTEMS	WCR

TYPICAL SEDIMENT TRAP DETAILS:


- REFERENCE -- RHODE ISLAND SOIL EROSION AND SEDIMENTATION CONTROL HANDBOOK.
- PROVIDE FOUR (4) TEMPORARY SEDIMENT TRAPS AS SHOWN ON SITE PLANS IN ACCORDANCE WITH THE FOLLOWING TOTAL INITIAL STORAGE VOLUME:
NW LOCATION: 201 CY MIN.
NE LOCATION: 402 CY MIN.
SE LOCATION: 349 CY MIN.
SW LOCATION: 335 CY MIN.
* ABOVE BASED ON 134 CY PER ACRE OF DRAINAGE VOLUME.
BASED ON ABOVE, ONE TYPICAL SEDIMENT TRAP SIZE TO ACCOMMODATE EACH AREA HAS BEEN SHOWN AS A 205 SF AREA. EACH AREA MUST INCLUDE WET STORAGE OF 1' DEPTH AND DRY STORAGE OF 1' DEPTH TO MEET THE MIN. DESIGN REQUIREMENTS.
- SPECIFIC DETAIL OF SEDIMENT TRAP CONSTRUCTION SHALL BE ACCORDANCE WITH THE DETAILS HEREIN AND SHOP DRAWING SUBMITTAL. REQUIRED FOR APPROVAL BY ENGINEER PRIOR TO INSTALLATION.

Figure 2. Minimum Top Width for Temporary Sediment Trap Embankments Based on Height of Embankment




(Credit: 2002 Connecticut Guidelines for Soil Erosion and Sediment Control)

Figure 3. Views of a Temporary Sediment Trap Outlet



(Credit: 2002 Connecticut Guidelines for Soil Erosion and Sediment Control)



Thomas J. Principe, III
No. 9107
PROFESSIONAL ENGINEER

PRINCIPE COMPANY, INC.
ENGINEERING DIVISION
PO BOX 298
TIVERTON, RI 02878
401.616.5385
PRINCIPLEENGINEERING@GMAIL.COM

REVISIONS

No.	DATE	DRWN	CHKD

KEACH DAM ROAD
GLOCESTER, RHODE ISLAND

DETAIL SHEET-3
SCALE: NTS
SHEET NO: 11 OF 11
DRAWN BY: TJP DESIGN BY: SL CHECKED BY: TJP
DATE: 3/10/16 PROJECT NO.: LD_2016_245